

GOVDOC

BRA

631

✓

NOV DEC

BRA

631

✓


Jan 10 1977

file
Garages

Parking Garage Study

Northeastern University

A study done in association with
VANASSE/HANGEN ASSOCIATES, INC.
Transportation Engineers & Planners



Keyes Associates — Architects/Engineers/Planners

Waltham
Massachusetts
Providence
Rhode Island
Wethersfield
Connecticut
Nashua
New Hampshire




Parking Garage Study

Northeastern University

A study done in association with
VANASSE/HANGEN ASSOCIATES, INC.
Transportation Engineers & Planners







Keyes Associates — Architects/Engineers/Planners

March 8, 1983
"Our Thirty-Second Year"

Mr. Clifford Fralen
Director of Physical Plant
Northeastern University
26 Tavern Road
Boston, MA 02115

SUBJECT: Parking Garage Study

Dear Mr. Fralen:

KEYES Associates is pleased to present the above study involving the site location and preliminary design for a 500 car parking garage to be located on University property off Columbus Avenue adjacent to the Southwest Corridor Project. During the course of our investigations we worked closely with Vanasse/Hangen Associates, Traffic Consultants, on vehicular and pedestrian circulation; with Haley and Aldrich on soils analysis and with your office for overall coordination.

The study included an evaluation of several different garage configurations to determine which would most closely satisfy the special requirements of the site. We have selected one of these alternate designs for your consideration and include cost estimates and a building systems description for the proposed facility. Recommendations were also made during the course of our study pertaining to the location and design of the pedestrian bridge to be constructed by the MBTA.

We look forward to a successful conclusion of negotiations by Northeastern University with the Authority and to continuing our efforts on the final design for the garage project.

Sincerely yours,

KEYES ASSOCIATES

Ernest E. Kirwan, AIA
Partner
EEK/jmp

267 Moody Street
Waltham, MA 02154
Telephone 617 893-2110

Other Offices: Providence, RI
Wethersfield, CT, Nashua, NH

Partners

Fenton G. Keyes, PE
Walter I. Keyes, PE
Ernest E. Kirwan, AIA
Leonard N. Buckler, PE

Associate Partners

Lewis J. Bain, PE
James L. Bell, PE
Richard H. Casale, AIA
Pasquale Codola, PE
David I. Grist, AIA
Len Kuhn, AIA, ASID, IBD
James R. Miller, PE
Leonard D. Warburton, PE

Senior Associates
Harry R. Jones, PE
Glenn C. Reeves, AIA
Robert B. Vogel, AIA
Jon T. Walworth, PE

Associates

James F. Low, PE
John J. Morra, PE
Albin E. Pilblad, PE
Dale S. Plante, LA
Domenic Procaccini, PE
James E. Ryan, PE
Joseph J. Votolato, PE

Consultant

Henry E. Bilodeau, PE

NORTHEASTERN UNIVERSITY
PARKING GARAGE STUDY

TABLE OF CONTENTS

- A. Campus Parking Space Analysis
 - Table 1. Parking Spaces-Loss and Gain
 - B. Site Planning
 - C. Garage Design and Construction
 - Table 2. Garage Floor Area and Parking Count
 - D. Cost Estimates
 - Table 3. Cost Breakdown
 - Table 4. Cost Comparison
 - E. Site and Garage Plans
 - Dwg. 1. Site Boundaries - 100' Scale
 - Dwg. 2. Proposed Site Plan - 100' Scale
 - Dwg. 3. Phase I. Ground Level Plan - 60' Scale
 - Dwg. 4. Phase I. Bridge Level Plan - 60' Scale
 - Dwg. 5. Building Section - 20' Scale
 - Dwg. 6. Phase II. Ground Level Plan - 60' Scale
 - Dwg. 7. Phase II Bridge Level Plan - 60' Scale
 - Dwg. 8. Perspective View
- Appendix. Alternative Garage Schematic

A. Campus Parking Space Analysis

The initial task in the study involved the review of all parking spaces presently available on the Campus and an analysis of spaces lost in the construction of the Southwest Corridor Project, the Engineering Building and the proposed Library and Recreation Center projects. In order to maintain existing total of approximately 3010 parking spaces, it was determined that a parking garage for approximately 500 cars will be required on Parcel 17X in the immediate future (Phase I); and that a future expansion of that garage (Phase II) of approximately 520 cars will be required when the Library (Initial Phase) is constructed. A future garage for 400 cars would be needed if the proposed Library Addition and Recreation Center were constructed. This garage (Phase III) would be located in the Parker Street-Field Street area for better Campus parking distribution.

TABLE 1. PARKING SPACE - LOSS AND GAIN

	N.U. Parking Loss	Public Parking Loss	N.U. Parking Gain	N.U. Subtotal	Garage Parking Gain	N.U. Total
Engineering Center	-128			-128		-128
Parcel X 2 (S.W. Corridor)			221	93		93
Garage Phase I (502)					390	483
Southwest Corridor SW 201 - 238 Tavern, Camden, etc.	-863	-149	248	-522		-132
Garage Phase II (519)					406	274
Library Phase I	-220			-742		54
Garage Phase III (400)					310	364
Recreation Center	-299			-1041		65
Library Phase II	-84			-1125		-19
Street Closings (tentative) Tavern Road Field Street		-41 -43	58 66	-1067 -1001		39 105

NOTE: The precise timetable for each of these projects is yet to be determined.

B. Site Planning

The first step in determining the optimal location for the proposed parking garage involved an examination of the existing site boundaries and characteristics.

The parcel, as shown on Site Plan (Drawing 1) is approximately 281,000 SF of land, bounded by the Southwest Corridor tracks, the new Ruggles Station and its approach road - Columbus Avenue and by the Carter Playground and Camden Street. Plans have been completed by the City for reducing the width of Columbus Avenue and include the provision of a 30' wide strip of land along the street - from the Carter Playground to St. Cyprian Street - in which will be located a bicycle path, sidewalk and landscaping.

The site is essentially flat, with grades ranging in elevation from 9'-11.5', National Geodetic Vertical Datum. The Ruggles Street Station will contain a bus ramp along the southwest edge of the site with a maximum elevation of 27.6' as it crosses the rail and transit tracks. The soil characteristics in the area have been documented in the report by Haley and Aldrich dated Aug. 6, 1981. These findings have been utilized in our study and indicate that spread footings can be successfully utilized in the garage design. Subsurface drainage will be required for both the garage and parking areas; access will be available to storm drains in Columbus Avenue.

In our site location studies for the garage, the following design criteria were utilized:

- Traffic control.
- Pedestrian circulation.
- Surface parking efficiency.
- Expandability of the garage.
- Visual factors - scale and exterior appearance.

A number of site locations and garage circulation systems were reviewed; six most promising alternatives were subjected to further scrutiny in meetings held with Transportation Planning Consultants, Vanasse/Hangen Associates. Their studies indicated that a significant amount of roadway length will be required within the site for stacking of vehicles entering the garage and surface parking areas. This requirement favored the construction of the "two-bay" garage layouts (122' wide) since the "three-bay" types utilized too much of the available site width, leaving insufficient land for properly engineered roadway design and surface parking layouts.

The Vanasse/Hangen report also illustrates the recommended location for ingress and egress driveways from Columbus Avenue. It is assumed that all incoming traffic of the site will be controlled from one set of gates and that the entire site will be fenced for security reasons. Several alternative locations for the two-bay garage were examined. The final recommended siting for the Phase 1

NORTHEASTERN UNIVERSITY PARKING GARAGE STUDY

garage was based on the most effective initial and long-term distribution of vehicles in the site and the location of pedestrian bridges across the tracks to the campus. There will be three bridges constructed by the MBTA as part of the Corridor Project; the first bridge will be located adjacent to the Ruggles Station bus ramp; the second at Camden Street; the third bridge was to be sited by the University. The best location for this bridge was determined to be opposite the roadway between the Ell Center and Robinson Hall, thereby providing easy access to the center of the campus and its tunnel system.

Sketches were prepared for the bridge location and its connection to the garage; these documents were forwarded through the University to PRC Harris, engineering consultants for the project. Design modifications for the bridge were also included since the proposed design (by the MBTA) was particularly unattractive; Keyes feels that the University should make a strong effort to upgrade the bridge design as recommended, since it will be a focal point for campus circulation for many years in the future. The bridge will connect with the third level of the proposed five-level garage (four decks above grade), and be reached by both the stairways and ramps to be constructed by the MBTA.

C. Garage Design & Construction

As stated earlier, KEYES considered many garage circulation schemes (See Alternate Garage schematics in Appendix). The most effective garage layout, based on all design criteria, was the two-bay split-level design shown on the enclosed drawings.

The 502-car capacity can be accommodated in Phase I, with a one-way traffic system utilizing up and down ramps at each end of the structure. As shown one of the ramps would be constructed at 25'-6" wide (instead of the normal 17'-0") to allow for a direct "exit spiral" when the Phase III garage is constructed. During our studies, we encountered some degree of difficulty in designing a garage which functions equally well in both Phases I and II. We feel, however, that the split level design will work most effectively in solving the following design requirements:

1. Filling up from the ground level-both phases, using student monitors.
2. No dead ends at the top floors (as found in sloping floor garages).
3. Ease of monitoring for security (split-levels are open, allowing visual access between levels).
4. Flat floor circulation to the stairs and bridges.
5. Attractiveness of the exterior design; no sloping facades.

NORTHEASTERN UNIVERSITY
PARKING GARAGE STUDY

TABLE 2. GARAGE SPACE AND PARKING COUNT

PARKING SPACES	PHASE I	PHASE II	TOTAL
GROUND	94	99	193
FIRST	102	105	207
SECOND	102	105	207
THIRD	102	105	207
FOURTH	102	105	207
TOTAL	<u>502</u>	<u>519</u>	<u>1021</u>
FOOTPRINT AREA	33,611	31,899	65,510
FLOOR AREAS			
FLAT PER LEVEL	29,862	29,740	59,602
X NO. OF LEVELS	<u>X 5</u>	<u>x 5</u>	<u>x 5</u>
TOTAL FLAT	149,310	148,700	298,010
RAMPS	13,940	7,480	21,420
TOTAL	<u>163,250</u>	<u>156,180</u>	<u>319,430</u>
SQUARE FEET/SPACE	325	301	313

The height of the garage at 44' (to the parapet wall) was determined to be in scale with the Ruggles Street Station (approximately 46' roof height) and nearby University buildings. The five-level design also occupies less land area than lower height garages thereby allowing a greater number of surface parking spaces.

The garage location, 17' from the "boat wall" of the Southwest Corridor, is sufficient for the placement of the spread footings and the pedestrian bridge ramps. Further study will be required on the effects of air and noise made by trains passing on the adjacent tracks since in the new design the south wall of the Corridor has been designed at a lower height than the north wall adjacent to the Campus (See Garage Section - Drawing 4).

The City of Boston requires that all garages be properly designed for fire resistance. Several construction systems have recently been utilized to meet this requirement; precast- prestressed concrete, the filigree-system, cast-in-place concrete, and fireproofed steel framing. KEYES, in conjunction with the Vappi Construction Company examined each of these systems and recommend the precast-prestressed system for reasons of initial cost, maintenance and overall appearance.

The garage would be constructed of precast-prestressed columns, spandrel beams and precast double tee beams, similar to the garage at the Winchester Hospital which was visited by a team from Northeastern University. The spandrel beams would be designed for attractive appearance with a pattern of smooth and textured concrete (either sandblasted or board-formed). The 4" thick double

tee beams form the wearing surface for the upper decks of the garage. These members are constructed with high strength (5000#) concrete and do not require a topping (such toppings have been subject to cracking in this climate). A special compound is used to seal the joints between the tees.

The lower or ground levels of the garage would be constructed utilizing bituminous concrete paving. Striping would be provided at all levels. High intensity discharge lighting units would be installed between the tee-beams at all levels creating a very economical and attractive lighting system for the structure. On the top deck, either wall mounted lighting units or low-pole units would be used. The stairwells would be constructed of concrete masonry units, either painted or finished with a Dryvit system exterior facing depending on final design concept. Trench drains would be installed at each level of the structure and brought to 5' outside the building line under the price shown on the cost estimate sheet. The drainage system connecting the garage to the street would be priced under the Site Development Budget. Fire Protection would include the standpipes required by the City of Boston. Painting of the stairwells is included, as is a budget for signage throughout the structure. Allowances are listed for landscaping and parking equipment.

D. Cost Estimates

The cost estimates listed below were prepared jointly by KEYES and VAPPI. The overall site work estimate was compiled by using a cost-per parking space figure based on our experience on other recent jobs. The site work would include bituminous paving over all areas except the Phase II garage site (which would remain as a gravel surface), drainage, lighting, striping and landscaping. It does not include the site fencing, since final determination of height, etc. has not been made to date. The garage estimates were prepared using recent experience by both the KEYES and VAPPI organizations.

TABLE 3. PRELIMINARY ESTIMATE

I.	SITE WORK		\$425,000
II.	PARKING GARAGE		3,160,700
		SUB TOTAL A	\$ 3,585,700
III.	CONTINGENCY -	3%	107,000
			\$ 3,692,700
IV.	A/E FEES -	5.2%	192,000
			\$ 3,884,700
V.	MISCELLANEOUS COSTS		
	BORING, TESTING, PRINTS		26,000
*	TOTAL COST		\$ 3,910,700

* Estimates based on 1983 award of contract. Cost for security fencing not included.

NORTHEASTERN UNIVERSITY
PARKING GARAGE STUDY


TABLE 4. Garage Estimates Cost Comparison

NORTHEASTERN UNIVERSITY PARKING GARAGE

<u>ITEM</u>	<u>PRECAST</u>	<u>FILIGREE</u>	<u>C.I.P.</u>	<u>FIREPROOFED STEEL</u>
Earthwork & Paving	124,500	124,500	124,500	124,500
Concrete & Re-Bar	286,300	311,500	311,500	311,500
Structure	1,925,000	1,972,700	2,051,600	2,206,700
Masonry	40,500	40,500	40,500	40,500
Miscellaneous Iron	55,000	55,000	55,000	55,000
Waterproofing	11,400	11,400	11,400	11,400
Caulking & Sealants	62,000	36,000	36,000	36,000
Doors, Frames, Hardware	3,900	3,900	3,900	3,900
Roofing & Flashing	3,600	3,600	3,600	3,600
Finishes & Graphics	22,000	22,000	22,000	22,000
Plumbing	64,500	64,500	64,500	64,500
Fire Protection	24,700	24,700	24,700	24,700
Electrical	167,500	167,500	167,500	167,500
Landscape Allowance	10,000	10,000	10,000	10,000
Parking Equipment Allowance	15,000	15,000	15,000	15,000
Sub-Total	2,815,900	2,862,800	2,941,700	3,096,800
Gen. Cond./Contr. Fee	<u>344,800</u>	<u>374,900</u>	<u>378,800</u>	<u>392,400</u>
	3,160,700	3,237,700	3,320,500	3,499,200

Budget estimates are for the building only - 5 feet outside the structure and include adjacent landscaped area.

Cost per car	6,296	6,450	6,615	6,971
Cost per Sq. Ft.	\$19.36	\$19.83	\$20.34	\$21.43



RECREATION CENTER

PORTINGALE

ANNEX

CHURCHILL

HAYDEN

ELL

ROBI

ROBI

SOUTH LOT

ENGINEERING

LIBRARY
PHASE 1

PHASE 2

RUGGLES STREET
MBTA STATION

MBTA ORANGE LINE

COMMUTER RAIL

HIGHTINGALE

RECREATION CENTER

ANNEX

CHURCHILL

HAYDEN

DANA

ENGINEERING

ELL

RUGGLES

SOUTH LOT

LIBRARY
PHASE 1

PHASE 2

RUGGLES STREET
MBTA STATION


MBTA ORANGE LINE

COMMUTER LINE

GARAGE/PHASE 2


GARAGE/PHASE 1


SOUTHWEST CORRIDOR



SOUTH LOT


ELL





SOUTHWEST CORRIDOR

WALPOLE STREET



LIBRARY

M.B.T.A ORANGE LINE

COMMUTER RAILROAD

194

195

196

197

198

199

2170

2171

2172

2173

2174

2175

UP



DN



UP




DN




UP





VIEW FROM COLUMBUS AVENUE




A

TWO-BAY WIDE
SPLIT LEVEL WITH
ONE-WAY RAMPS

KEYES

Keyes Associates - Architects/Engineers/Planners

Providence, R.I.
Waltham, Mass.
Wethersfield, Ct.
Nashua, N.H.




(B)

THREE-BAY WIDE
FLAT FLOOR WITH
ONE-WAY TRAFFIC
RAMPED FLOORS

KEYES

Keyes Associates - Architects/Engineers/Planners

Providence, R.I.
Waltham, Mass.
Wethersfield, Ct.
Nashua, N.H.




©

THREE-BAY WIDE
FLAT FLOOR WITH
TWO-WAY TRAFFIC
RAMPED FLOOR

KEYES

Keyes Associates - Architects/Engineers/Planners

Providence, R.I.
Waltham, Mass.
Wethersfield, Ct.
Nashua, N.H.




(D)

TWO-BAY WIDE
SPLIT LEVEL WITH
TWO-WAY CENTER RAMP

KEYES

Keyes Associates - Architects/Engineers/Planners

Providence, R.I.
Waltham, Mass.
Wethersfield, Ct.
Nashua, N.H.




(E)

TWO-BAY WIDE
RAMPED FLOOR WITH
TWO-WAY TRAFFIC
(SINGLE SPIRAL)

KEYES

Keyes Associates - Architects/Engineers/Planners

Providence, R.I.
Waltham, Mass.
Wethersfield, Ct.
Nashua, N.H.




(F)

TWO-BAY WIDE
RAMPED FLOOR WITH
ONE-WAY TRAFFIC
(DOUBLE SPIRAL)

KEYES

Keyes Associates - Architects/Engineers/Planners

Providence, R.I.
Waltham, Mass.
Wethersfield, Ct.
Nashua, N.H.




TYPICAL FLOOR
1"=40'
GARAGE 'A'

KEYES

Keyes Associates - Architects/Engineers/Planners

Providence, R.I.
Waltham, Mass.
Wethersfield, Ct.
Nashua, N.H.

287'




TYPICAL FLOOR
1"=40'
GARAGE 'B'

132'

KEYES

Keyes Associates - Architects/Engineers/Planners

Providence, R.I.
Waltham, Mass.
Wethersfield, Ct.
Nashua, N.H.




TYPICAL FLOOR $\frac{1}{4}'' = 40'$

GARAGE

BARNET VAULT
TIP ELEV. 66.42'

ROOF ELEV. 38.42'

RUGGLES ST.
STATION



SECTION
1" = 40'

GARAGE 'A'

KEYES


Keyes Associates - Architects/Engineers/Planners

Providence, R.I.
Waltham, Mass.
Wethersfield, Ct.
Nashua, N.H.

BARREL VAULT
TOP ELEV. 56.42'

ROOF ELEV. 38.42'

RUGGLES ST.
STATION



SECTION
1" = 40'
GARAGE 'B'

BOSTON PUBLIC LIBRARY



3 9999 06314 702 7

